

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
NOV 18 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name George R. ShawComplete Address 826 Union Center, Wichita, Kansas 67202Lease Name Edna Brown Well No. 2Location C NE NE Sec. 22 Twp. 26 Rge. 9 (E) (W) XCounty Reno Total Depth 3270'Abandoned Oil Well Gas Well X Input Well SWD Well D & A Other well as hereafter indicated Plugging Contractor Pipe Pullers, Inc.Address Box 486, Ellinwood, Kansas License No. 462Operation Completed: Hour 5 PM Day 12 Month November Year 1970

The above well was plugged as follows:

5½" plug pushed to 2440'. Hole filled with sand to 2400' and cemented with 10
sacks cement. Hole bailed to 290'. Rock bridge set from 290' to 280' and hole
cemented with 25 sacks cement.. Hole filled with mud to 40'. Rock bridge set
from 40' to 30' and hole cemented to base of cellar with 10 sacks cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging SupervisorDATE 11/18/70INV. NO. 2877-41