

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 12 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Robert F. White 15-155-30116-0000

Complete Address 714 Union Center, Wichita, Kansas 67202

Lease Name Clough-Jones Well No. 1

Location C NE/4 Sec. 24 Twp. 26 Rge. 9 (E) (W) X

County Reno Total Depth 2462'

Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Knight Casing Pulling Co., Inc.

Address Box 405, Chase, Kansas License No. 624

Operation Completed: Hour Noon Day 10 Month February Year 1971

The above well was plugged as follows:

4 1/2" plug pushed to 1995'. Hole filled with sand to 1950' and cemented with 3 sacks  
cement. Hole bailed to 225'. Rock bridge set from 225' to 215' and hole cemented  
with 25 sacks cement. Hole filled with mud to 40'. Rock bridge set from 40' to 30'  
and hole cemented to base of cellar with 10 sacks cement.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 2/12/71  
INV. NO. 3332-U