

B

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15-155-20,574-0000 (of this well)

Operator's Full Name Martin-Visa  
Complete Address P.O. Box 36028, Denver, Colorado  
Lease Name Clay Pool Well No. 1  
Location NW NE SE Sec. 31 Twp. 26 Rge. 9 (E) (W) K  
County Reno Total Depth 4235'

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Catlett Drilling Company

Address P.O. Box 366, Augusta, Kansas License No. 755

Operation Completed: Hour 5 PM Day 5 Month March Year 1979

The above well was plugged as follows: 8 7/8" - 321' - cement circulated 4 1/2" - 1680' - 150 sacks  
Fill hole with sand to 1550' and cement with 3 sacks cement.  
Fill hole with mud to 310'. Set rock bridge from 310' to 300' and  
cement hole with 25 sacks cement. Fill hole with mud to 40'.  
Set rock bridge from 40' to 30' and cap hole with 10 sacks cement.  
1470' of 4 1/2" casing recovered

3-8-79

RECEIVED

STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

MAR - 8 1979

INVOICED

Signed: [Signature]  
Well Plugging Supervisor  
CONSERVATION DIVISION  
STATE CORPORATION COMMISSION  
KANSAS

DATE 3-9-79  
INV. NO. 9236-W