

KANSAS

FORM CP-3
Rev. 11-3-80STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORTAPI Number 15-155-20,758-0000200 Colorado Derby Bldg.
Wichita, KS 67202Operator's Full Name Murfin Drilling CompanyComplete Address 617 Union Center, Wichita, Kansas 67202Lease Name Abendshein Well No. 1Location C NW NW Sec. 11 Twp. 26 Rge. 10 (~~EAST~~) (West)County Reno Total Depth 4235'Abandoned Oil Well ☐ Gas Well ☐ Input Well ☐ SWD Well ☐ D & A ☒ X

Other well as hereafter indicated _____

Plugging Contractor Co. Tools and Halliburton Co.

Address _____ License No. _____

Operation Completed: Hour: 7:00 AM Day: 24 Month: April Year: 1981The above well was plugged as follows: 8-5/8"-292'-250 sacks common circ.Hole filled with mud. 50 sacks 50-50 pozmix W/2% gel pumped through
drill pipe at 530'. 40 sacks cement pumped through drill pipe at 290'.Hole filled with mud to 40'. Plug and 1/2 sack hulls pushed to 40' and
hole cemented to base of cellar with 10 sacks cement. Rathole cemented
with 10 sacks cement. Mousehole cemented with 5 sacks cement.RECEIVED
STATE CORPORATION COMMISSION

4-29-81 APR 29 1981

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5-28-81INV. NO. 5529-WSigned: [Signature]
Conservation Division Agent