



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

14 November 1981

VERBAL PERMIT FORM (To be filed by Plugging Agent)

15-097-20825-0000

Dear Sir:

Mr. Tommy Thompson of H-30 Drilling Co Rig 77 has this date requested permission to plug the following described well:

Operator's Full Name: Ka-Tex Energy

Complete Address: R. #2 box 41 Lewis Kansas

Lease Name: Ashworth Well No. 1

Location: C-SE-SE SE Sec. 20 Twp. 27 S Rge. 17 W (E) (W)

County: Keiwa Total Depth: 4861'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Thompson was instructed to plug the well as follows:

There is 426' of 8 5/8" surface casing cement circulated with 375 lbs of cement. 1st plug at 920' with 60 lbs of cement. 2nd plug at 400' with rubber plug pushed to this depth and 50 lbs of cement. 3rd plug at 40' to 0' with 10 lbs of cement. Then pumped 10 lbs ^{Cement} in rat hole & 5 lbs cement in mouse hole. Plugging accomplished by Dowell well out of Great Bend Kans
The cement used was common with 2 3/4 Gall & 3 3/8 c.c.

Very truly yours,

RECEIVED
STATE CORPORATION COMMISSION

NOV 17 1981

Paul Luthi
Conservation Division Agent

CONSERVATION DIVISION
Wichita, Kansas

11-17-81