

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

SEP 30 1963
 9-30-63
 CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Deacon of Forbes Casing Pulling has this date requested permission to plug the following described well:

Mr. Deacon guarantees payment of the plugging fee.

Operator's full Name: Messman-Rinehart Oil Co.

Complete Address: 1432 Wichita Plaza, Wichita, Kansas

Lease Name: Lion Fee "A" Well No. # 1

Location: SE SE NW Sec. 21 Twp. 27 Rge. 11 (E) (W) W

County Pratt Total Depth 4450 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Deacon was instructed to plug the well as follows:

180' of 13 3/8" surface pipe, cemented to top. 4450' of
5 1/2" long string, cemented with 150 sacks. Plugged back to
3975'. Top perforation 3796'. Sand to 3780', cement with
5 sacks. Fill hole with mud to 225', 10' rock bridge, cement
with 40 sacks. Fill hole with mud to 40', 10' rock bridge,
cement with 20 sacks to base cellar.

Very truly yours,

Archie Elving
 Conservation Division Agent