

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

RECEIVED  
 STATE CORPORATION COMMISSION

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

FEB 11 1963

CONSERVATION DIVISION  
 Wichita, Kansas

2-11-63

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Kelso of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Kelso guarantees payment of the plugging fee.

Operator's full Name: Bowers Drilling Co. Inc.

Complete Address: Union Central Bldg., Wichita, Kansas

Lease Name: Pyle Well No. # 1

Location: NW SE SE Sec. 10 Twp. 27 Rge. 16 (E) (W) W

County Kiowa Total Depth 4695 Oil Well X

Gas Well    Input Well    SWD Well    D & A    Lost Hole   

Mr. Kelso was instructed to plug the well as follows:

4677' of 4 1/2" long string. Plugged back to 4542'. Top of  
perforation 4537'. Sanded to 4530'. cemented with 3 sacks.  
370' of 8 5/8" surface pipe circulated with cement. Fill  
to 200' with mud, 10' rock bridge, cement with 20 sacks.  
Fill hole to 40' with mud, 10' rock bridge, cement with 10  
sacks to base of cellar.

Very truly yours,

Audie Elving  
 Conservation Division Agent