


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Kingman County. Sec. 14 Twp. 27 Rge. 10 (E)W (W)



Locate well correctly on above  
Section Plat

Location as "NE/CNWxSWx" or footage from lines -SW NW SW  
Lease Owner Lawrence Supply Co., Inc.  
Lease Name Sale #2 Well No. \_\_\_\_\_  
Office Address Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 2-9-59 19\_\_\_\_  
Plugging completed 2-13-59 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hample  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4277 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	192'	none
				5-1/2"	4276'	3520'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked the hole to 4275' and found it open.  
Filled w/sand to 4265' and dumped 5 sacks of  
cement with bailer. Pulled 50 jts of 5 1/2"  
casing, and pumped in 30 sacks of gel mud.  
Pulled rest of casing, cleared hole and  
bailed fluid to 190', set rock bridge to  
180' and dumped 20 sacks of cement. Mudded  
the hole to 40', set rock bridge to 30' and  
ran 10 sacks of cement to base of cellar.

**RECEIVED**  
STATE CORPORATION COMMISSION  
FEB 18 1959  
CONSERVATION DIVISION  
WICHITA, KANSAS

PLUGGING COMPLETED

Name of Plugging Contractor West Supply Co., Inc.  
Address Chase, Kansas

STATE OF KANSAS COUNTY OF RICE ss.  
I, Noel J. Knight (employee of owner) or ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of February, 19 59

9-27-62

Thomas V. Maguire  
Notary Public.

My commission expires \_\_\_\_\_

PLUGGING  
FILE SEC. 14 T. 27 R. 10W  
BOOK PAGE 14 LINE 25

Bennett & Roberts Oil Operations  
Sale #2

SW NW SW Sec. 14-27-10  
Kingman County, Kansas

R. T. D. 4277½

Comm: 7/27/54  
Comp: 8/13/54

Set 8 5/8" Csg. @ 198° w/225 sx. cmt.  
Set 5 1/2" Csg. @ 4276½ w/100 sx. cmt.

Formation:	Depth:
Sand	30'
Shale	200
Red Bed	385
Red Bed & Shale	710
Anhydrite & Shale	750
Shale	910
Red Bed & Shale	1415
Lime, Shells & Shale	1785
Lime & Shale	2205
Shale	2530
Lime & Shale	2800
Sand & Shale	2925
Lime & Shale	3009
Lime	3430
Lime & Shale	3505
Lime	4059
Lime & Shale	4110
Shale	4170
Shale & Lime	4268
Lime	4277½

RECEIVED  
STATE CONSERVATION COMMISSION  
FEB 6 1958  
CONSERVATION  
Wichita

STATE OF KANSAS )  
COUNTY OF RUSSELL ) SS.

I hereby certify that the above information is correct to  
the best of my knowledge.

BENNETT & ROBERTS OIL OPERATIONS

Sylvia Day

Subscribed and sworn to before me this 24th day of August, 1954.

Mara Hansen  
Notary Public

My Commission Expires 6/17/58

PLUGGING  
FILE SEC. 14 T. 27. R. 10W  
BOOK PAGE 14 LINE 25