


KANSAS STATE CORPORATION COMMISSION  
Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 North Market, Insurance Bldg.  
Wichita, Kansas

**WELL PLUGGING RECORD**



Kingman County. Sec. 14 Twp. 27 Rge. (E) 10 (W)  
Location as "NE/CNW/SW" or footage from lines SW - NE - NE  
Lease Owner Morganstern & Spector, Inc.  
Lease Name Cannon Well No. 6  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed 11-19-51  
Application for plugging filed Nov. 10, 1959  
Application for plugging approved Nov. 12, 1959  
Plugging commenced  
Plugging completed  
Reason for abandonment of well or producing formation failure to produce profitably  
If a producing well is abandoned, date of last production  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel  
Producing formation 4202a Depth to top 4282 Bottom 4283 Total Depth of Well 4285 Feet  
Show depth and thickness of all water, oil and gas formations.

**OIL, GAS OR WATER RECORDS**

**CASING RECORD**

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				9 5/8	290	None
				5 1/2	4283	3216.78

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with sand from 3810' to 3725' - dumped 5 sacks of cement - mudded hole to 250' - set 10' rock bridge - dumped 20 sacks of cement - mudded to 30' - set rock bridge - dumped 10 sacks of cement to base of cellar.

**RECEIVED**  
STATE CORPORATION COMMISSION  
JAN 19 1960  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor R & D Casing Pulling Co. License # 236  
Address Box 154 Ellinwood, Kansas

STATE OF Kansas COUNTY OF Russell, ss.  
Morgenstern & Spector, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Morganstern*

(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of December, 19 59

My commission expires July 18, 1961  
Jessie Lee Dunn Notary Public.



WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
 500 East Myrdock, Wichita, Kansas


COPY

Company- LION OIL CO.  
 Farm- Cannon No. 6

SEC. 14 T. 27 R. 10W  
 SW NE NE

Total Depth, 4285  
 Comm. 11-6-51 Comp. 11-19-51  
 Shot or Treated.  
 Contractor, R. W. Rine Drlg. Co.  
 Issued. 5-3-52

County Kingman  
 KANSAS



CASING:  
 9 5/8" 290' cem. w/250 sx  
 5 1/2" 4283' cem. w/200 sx

Elevation. 1753  
 Production. 138 BO & 58% wtr.  
 Phy. Pmp.

Figures indicate Bottom of Formations.

sand	150
sand & shale	300
shale	310
shale & shells	1000
shale, shells & salt	1380
lime	1450
lime & shale	1800
lime	1940
shale & lime	2435
shale	2665
shale & lime	3700
lime	3734
lime & shale	3790
lime	3930
lime & shale	4030
miss. chert	4060
lime & shale	4284 RTD
lime & shale	4285
Total Depth	

Tops:

Brown Limo	3488
Lansing	3495
Miss.	4019
Viola	4282

DP & DD 4285- SSO, 500 acid,  
 Swab 12 bopd / 24 bwpd, Swab  
 6 bo / 12 bw 20 hrs., 1,500  
 acid, Swab 18 bopd / 18 bwpd POP

STATE CORPORATION COMMISSION  
 DEC 4 1959  
 CONSERVATION DIVISION  
 Wichita, Kansas