


R

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Kingman County, Sec 14 Twp 27 Rge 10 (E) (W)
Location as "NE/CNW&SWK" or footage from lines CW/2 SE SE
Lease Owner Morganstern & Spector
Lease Name Bick Well No. 4
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 8-25-51 19
Application for plugging filed Nov. 10, 1959 19
Application for plugging approved Nov. 12, 1959 19
Plugging commenced 12/14/59 19
Plugging completed 12/17/59 19
Reason for abandonment of well or producing formation failure to produce profitably
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred W. Hampel
Producing formation Viola Depth to top 4275 Bottom 4276 Total Depth of Well 4279 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8" OD	295'	none
				5 1/2" OD	4276'	3234.59'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged back to 3171 ft. dumped 5 sacks cement. Set fresh water plug 450 ft.
Set 10 ft. rock bridge. Dumped 20 sacks cement. Mudded hole to 35 ft.
set rock bridge dumped 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
JAN 19 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor E & L Casing Pulling Co.
Address 1416 Coolidge, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
Morgenstern & Spector, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) *Edith Morgenstern*
(Address) *Russell*

Subscribed and Sworn to before me this 24th day of December, 1959
My commission expires July 18, 1961
Jessie Lee Dunn
Jessie Lee Dunn Notary Public.

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock Wichita, Kansas


COPY

Company - LION OIL COMPANY
Farm - Bick No. 4

SEC. 14 T. 27 R. 10W
CW/2 SE SE

Total Depth. 4279
Comm. 8-15-51 Comp. 8-25-51
Shot or Treated. Acid 1000
Contractor. R. W. Rine Drilling Co.
Issued. 9-29-51

County. Kingman
KANSAS



CASING:
8 5/8" 295' cem w/250 sx.
5 1/2" 4276' cem w/200 sx.

Elevation. 1741

Production BHB Pot. 6400 bbls

Figures Indicate Bottom of Formations.

sand	150
red bed, shells	200
red bed	550
redbed, shale,	
shells	1330
lime	1950
shale	3065
lime, shale	3680
lime	3985
shale, lime	4011
miss. lime, chert	4060
shale, lime	4176
shale	4279
Total Depth	

Tops:	
Lansing	3496
Mississippian	4009
Viola	4275

RECEIVED
STATE CORRELATION COMMISSION

DEC 21 1959

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 1/14/60

INV. NO. 700-W