


STATE OF KANSAS
STATE CORPORATION COMMISSION

R
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail Deliber Report to:
Conservation Division
State Corporation Commission
111 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Flat

Kingman County. Sec. 11 Twp. 27 Rge. 10 (E) (W)
Location as "NE/CNW/SW" or footage from lines SW NE SE
Lease Owner Morgenstern & Spector
Lease Name Bick #3 Well No. _____
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 8-15-51 19____
Application for plugging filed Nov. 10, 1959 19____
Application for plugging approved Nov. 12, 1959 19____
Plugging commenced 12-15-59 19____
Plugging completed 12-17-59 19____
Reason for abandonment of well or producing formation failure to produce profitably
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hample
Producing formation Viola Depth to top 4271 Bottom 4272 Total Depth of Well 4275 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	OD 304'	None
				5-1/2"	4272	3228'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked the hole to 4275' and found it open.
Filled w/sand to 4250' and dumped 5 sacks of cement with bailer. Pulled 5 1/2" casing.
Cleared hole and mudded the hole to 180', set rock bridge to 170' and dumped 20 sacks of cement. Mudded the hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETED

RECEIVED
STATE CORPORATION COMMISSION
1-19-60
JAN 19 1960

Name of Plugging Contractor Knight Casing Pulling Co. (If additional description is necessary, use BACK of this sheet)
Address Chase, Kansas CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS COUNTY OF RICE, ss.
I, Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
Chase, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 24th day of December, 19 59

My commission expires 9-27-62 Thomas V. Dugg Notary Public.




WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- LION OIL CO.
 Farm- Bick No. 3

SEC. 14 T. 27 R. 10W
 -SW NE SE

Total Depth. 4275
 Comm. 8-3-51 Comp. 8-15-51
 Shot or Treated.
 Contractor. The R. W. Rine Drlg. Co.
 Issued. 11-3-51

County Kingman
 KANSAS



CASING:
 8 5/8" 304' cem. w/250 sx
 5 1/2" 4272' cem. w/200 sx

Elevation. 1730

Production. Pot. 188 BO & 14% W.

Figures Indicate Bottom of Formations.

sand, clay & red bed	313
shale	1300
shale & lime	1600
lime & shale	3000
lime	3100
lime & shale	3340
lime	3430
lime & shale	3650
lime	3995
lime, chert	4050
lime	4090
shale	4212
shale & lime	4250
lime	4275
Total Depth	

Tops:	
Lansing	3492
Miss.	4002
Viola	4271

Acidized w/1000 gals.

RECEIVED
 STATE CORPORATION COMMISSION

JAN 7 1960

CONSERVATION DIVISION
 Wichita, Kansas