


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

**WELL PLUGGING RECORD**

NORTH



Locate well correctly on above  
Section Plat

Kingman County. Sec. 14 Twp. 27 Rge. 10 (E) (W) XX  
Location as "NE/CNW/WSW" or footage from lines NE NE Se  
Lease Owner Morganstern & Spector  
Lease Name Bick Well No. 1  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed 7-21-51 19\_\_  
Application for plugging filed Nov. 10, 1959 19\_\_  
Application for plugging approved Nov. 12, 1959 19\_\_  
Plugging commenced 12/28/59 19\_\_  
Plugging completed 12/9/59 19\_\_  
Reason for abandonment of well or producing formation failure to produce  
profitably  
If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? \_\_\_\_\_

Name of Conservation Agent who supervised plugging of this well Fred W. Hampel  
Producing formation Viola Depth to top 4272 Bottom 4275 Total Depth of Well 4276 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 5/8" OD	300	none
				5 1/2" OD	4275	2947 feet

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back to 4250 ft. Dumped 5 sacks of cement. Mudded hole to 240 ft. set rock bridge at 240 ft. Dumped 20 sacks cement. Mudded hole to 35 ft. dumped 10 sacks cement.

**RECEIVED**  
STATE CORPORATION COMMISSION  
1-19-60  
JAN 19 1960

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor E & L Casing Pulling Co. CONSERVATION DIVISION  
Address 1416 Coolidge, Great Bend, Kansas Wichita, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.  
Morganstern & Spector, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Arthur Morganstern  
Box 661 - Russell - Mo  
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of January, 1960

My commission expires 3-15-63  
J. E. Sheppard  
Notary Public.



WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
508 East Murdock Wichita, Kansas


COPY

Company - LION OIL CO.  
Farm - Bick No. 1

SEC. 14 T. 27 R. 10W  
NE NE SE

Total Depth. 4276  
Comm. 7-9-51 Comp. 7-21-51  
Shot or Treated.  
Contractor. The R. W. Rine Drlg. Co.  
Issued. 9-22-51

County. Kingman  
KANSAS



CASING:  
9 5/8" 300' com. w/250 sx  
5 1/2" 4275' com. w/200 sx

Elevation. 1742

Production. BHB Pot. 1989 BOPD

Figures Indicate Bottom of Formations.

surface sand & clay	90
sand	160
red rock & shells	308
red bed & shells	425
red bed & shale	1470
lime	1670
lime, shale	2075
shale	2425
shale & lime	3500
lime	3650
lime & shale	3755
lime	3880
lime & shale	3942
lime	4012
lime & chert	4050
shale	4055
lime	4225
shale	4276
Total Depth	

Tops:	
Lansing	3500
Mississippi	4015
Viola	4272

Acidized w/750 gals.

**RECEIVED**  
STATE CORPORATION COMMISSION  
DEC 11 1959  
CONSERVATION DIVISION  
Wichita, Kansas

**INVOICED**  
DATE 1/14/60  
INV. NO. 697-W