


WELL PLUGGING RECORD

STATE OF KANSAS  
CORPORATION COMMISSION  
Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

STATE CORPORATION COMMISSION  
WICHITA, KANSAS  
JUL 20 1957  
7-20-57

Kingman County, Sec. 22 Twp. 27 Rge. 10 (E) W (W)  
Location as "NE/CNW%SW%" or footage from lines NE NE NE  
Lease Owner Tennessee Gas Transmission Co.  
Lease Name M. A. Richardson #1 Well No. 1  
Office Address Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 3-24-57 19  
Application for plugging filed 7-6-57 19  
Application for plugging approved 7-9-57 19  
Plugging commenced 7-11-57 19  
Plugging completed 7-15-57 19  
Reason for abandonment of well or producing formation Depletion



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production ----- 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Merle Rives  
Producing formation ----- Depth to top ----- Bottom ----- Total Depth of Well 4324 Feet  
3950 PB  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				9-5/8"	323	none
				7"	4323'	1809'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ----- feet to ----- feet for each plug set.

Checked the Hole to 4000'. Lane Wells set a plug at 3950'. Ran 3 sacks of cement on plug to 3935'. Filled casing. Baled hole to 310', set a 10' rock bridge and ran 20 sacks of cement. Mudded to 35', set a 10' rock bridge and ran 10 sacks of cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor West Supply Co., Inc.  
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.  
Glen E. Armour (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Glen E. Armour

SUBSCRIBED AND SWORN to before me this 17th day of July, 1957

Thomas V. Haggin Notary Public.

My commission expires 9-27-58

PLUGGING  
FILE SEC 32 T 27 R 10W  
BOOK PAGE 25 LINE 35