


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

All Information Completely
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Reno County, Sec. 30 Twp. 25s Rge. (E) 4 (W)
Location as "NE/CNW&SW&" or footage from lines NE SE NE
Lease Owner FLEMING-WOODMAN
Lease Name HILGERS-CRON Well No. 2
Office Address 717 Union National Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed June 11, 19 59
Application for plugging filed June 11, 19 59
Application for plugging approved June 11, 19 59
Plugging commenced June 11, 19 59
Plugging completed June 11, 19 59
Reason for abandonment of well or producing formation No commercial quantity
of gas and/or oil was encountered.
If a producing well is abandoned, date of last production - 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Lancamp, Stafford, Kansas
Producing formation - Depth to top - Bottom - Total Depth of Well 40-34' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 3/4"	253	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used
in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Set bottom plug at 245' with 1/4 sack of hulls and 20 sacks of cement through drill
pipe. Set top plug at 35' with 1/2 sack of hulls and 10 sacks of cement through drill pipe.

RECEIVED
STATE CORPORATION COMMISSION


JUN 19 1959
6-19-59
CONSERVATION DIVISION,
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor WILKINSON DRILLING, INC.
Address 1121 Union National Building, Wichita 2, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
K. T. Woodman (employee of owner) or (owner or operator) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.
(Signature) K. T. Woodman
714 Union National Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 18th day of June, 19 59
My commission expires January 2, 1961
Carolyn F. Moore
Notary Public.

PLUGGING
FILE SEC 30 T 25 R 4W
BOOK PAGE 1 LINE 22



WILKINSON DRILLING, INC.
1121 Union National Building
Wichita 2, Kansas

June 15, 1959

HILGERS-CRON #2

Company	-- FLEMING-WOODMAN	Location	-- NE SE NE, Sec. 30-25 ^s -4w,
Contractor	-- WILKINSON DRILLING, INC.		Reno County, Kansas
Commenced	-- May 27, 1959	Elevation	-- 1434' KB
Completed	-- June 11, 1959	Casing	-- 8 5/8" @ 253' w/200 ska
Total Depth	-- 4034'		

FIGURES INDICATE BOTTOMS OF FORMATIONS

<u>Depth</u>	<u>Formations</u>
0 - 60	Surface clay and shale.
60 - 253	Shale.
253 - 640	Shale and shells.
640 - 670	ANHYDRITE.
670 - 845	Shale and shells.
845 - 1220	Shale and lime.
1220 - 2297	Lime and shale.
2297 - 2515	Lime.
2515 - 2660	Lime and shale.
2660 - 2755	Lime.
2755 - 2937	Lime and shale.
2937 - 3567	Lime.
3567 - 3610	Lime, shale, and Mississippi.
3610 - 3669	Mississippi and lime.
3669 - 3749	Mississippi.
3749 - 3780	Lime.
3780 - 3803	Lime and chert.
3803 - 3870	Lime (Mississippi).
3870 - 4010	Lime and shale.
4010 - 4034	Viola.

6-19-59
 RECEIVED
 STATE DEPARTMENT OF REVENUE
 CONSERVATION DIVISION
 JUN 19 1959
 Wichita, Kansas

We hereby certify the above and foregoing to be a true and correct copy of the Log on the HILGERS-CRON #2, located in the NE SE NE, Sec. 30-25^s-4w, Reno County, Kansas.

WILKINSON DRILLING, INC.

Walter M. Wilkinson
Walter M. Wilkinson

Subscribed and sworn to before me this fifteenth day of June, nineteen hundred and fifty-nine.

Carolyn K. Moore
Carolyn K. Moore

My commission expires January 2, 1961.

PLUGGING
FILE SEC 30 T25 R 4w
BOOK PAGE 1 LINE 22