


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitling Building
Wichita, Kansas

Reno County. Sec. 26 Twp. 26 Rge. (E) 4 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW NW SE
Lease Owner Earl F. Wakefield
Lease Name Sigg Well No. 1
Office Address
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 13 1951
Application for plugging filed February 13 1951
Application for plugging approved February 13 1951
Plugging commenced February 13 1951
Plugging completed February 13 1951
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J. P. Roberts
Producing formation Depth to top Bottom Total Depth of Well 3795 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	126'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 145 feet set wood plug with 15 sacks of cement, filled hole to 20 feet with mud 5 sacks cement fill balance with mud

RECEIVED
STATE CORPORATION COMMISSION
FEB 20 1951
CONSERVATION DIVISION
WICHITA, KANSAS
2-20-51

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Earl F. Wakefield
Address 307 Union National Bank Building
Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
E. M. Callaway (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. M. Callaway
307 Union National Bk. Bldg. Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 14th day of February, 1951

My commission expires 12-23-54

PLUGGING
FILE SEC 26 Twp 26 R 4 W
BOOK PAGE 61 LINE 27

[Signature]
Notary Public

Sigg #1
 Owner: Earl F. Wakefield
 Contractor: Earl F. Wakefield
 Comm: 1-31-51 Comp: 2-13-51

NW NW SE 26-26S-4W
 Reno County, Kansas
 Casing: 126' of 8 5/8"

Surface	145
Red Bed and Shale	300
Shale & Shells	1095
Lime & Shale	1200
Lime	1490
Shale & Lime Streaks	1560
Lime & Shale	1635
Shale & Shells	1820
Shale	1940
Lime & Shale	2150
Shale & Shells	2275
Lime & Shale	2345
Shale & Shells	2460
Lime & Shale	2830
Shale	2900
Lime & Shale	2965
Lime	3135
Lime & Shale	3565
Shale	3716
Lime	3740
Chert	3758
Dolomite	3795
T. D.	3795

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct copy of the log of the Sigg #1 well located NW NW SE 26-26S-4W, Reno County, Kansas.

E. M. Lawrence

Subscribed and sworn to before me this 14th day of February, 1951

B. James Gaffney

My commission expires: 12-23-54

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 20 1951
 CONSERVATION DIVISION
 Wichita, Kansas

2-20-51

PLUGGING
 FILE SEC 26 T 26 R 40
 BOOK PAGE 61 LINE 27