

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-155-00118 ⁰⁰⁰⁰

LEASE NAME Schwaiger

WELL NUMBER # 1

SPOT LOCATION SE NE NW

SEC. 28 TWP. 26 RGE. 4 (E) or (W)

COUNTY Reno

Date Well Completed 3-4-60

Plugging Commenced 10-28-83

Plugging Completed 2-27-84

CORRECTED COPY

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Bell Brothers

ADDRESS Box 581, Robinson, Ill. 62454

PHONE #618, 544-2157 OPERATORS LICENSE NO. 5452

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? One

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4186'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	187'	None
				5-1/2"	4173'	3335.34

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Dumped sand to 3950' and 5 sacks cement Shot casing at 3400'. Pulled 108 joints of 5-1/2" casing. Squeezed well with 3 sacks hulls, 6 sacks gel and 125 sacks common cement with 3% calcuim chloride Capped well with 2-1/2 yards readymix concrete.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Ks. 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well and that the same are true and correct, so help me God. STATE CORPORATION COMMISSION

(Signature) James W. Rockhold
(Address) James W. Rockhold
Box 698, Great Bend, Ks. 67530

MAR 08 1984
3-8-84

SUBSCRIBED AND SWORN TO before me this 7th day of March, 1984
Wichita, Kansas

STATE NOTARY PUBLIC
KANSAS
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-26-87

Iona M. Leatherman
Notary Public

My Commission expires:

L'd

2-20-84

Mr. Pippageorge called concerning your letter. Rockhold Engineering, Great Bend will take care of paragraph two.

The water well belong to Leamer, John Hilger for last ten years, he should take care of paragraph three.

Mid-State Construction, Great Bend, will take care of tank battery in fourth paragraph.

Rockhold Engr. - Gt Bend

316-792-2506

James W. Rockhold - Pres.

Mid-States Sales & Service - Gt. Bend.

316-793-6001 - 316-793-8610

Clet Younger - Pres.

F. E. WEISHAUPT
442 AVE. C EAST
KINGMAN, KANSAS 67068
316-532-3737
February 23, 1984

Ralph O'Connor

On February 9, 1984 an abandoned oil well and open fresh water well were found in SE NE NW of Sec. 28-26-4w of Reno county.

It was detemined that this property had been abandoned by Bell Brothers Box 581 Robinson, Illinois.

On February 13, 1984 a letter was written to Mr. S. Charles Pappageorge who is co-owner and president of Bell Brothers, explaining that the cement in the oil well was 115' below the surface and needed to be filled to the surface with cement and that the steel casing in the water well should be pulled and the well filled to the surface with cement.

On February 20, 1984, Mr. Pappageorge called the Wichita office and reported that Rockhold Engineering of Great Bend would fill the oil well to the surface with cement.

Mr. Pappageorge stated that about 10 years ago the property, this well is on, was sold to Mr. John Hilger and that the water well was included in the transaction and that the water well was his responsibility.

Mr. Hilger lives on the property. His mailing adress is Route #1, Mt. Hope, Kansas 67108 and his home telephone is 316-445-2255.

I will go ahead and contact Rockhold Engineering to have the oil well cemented but will turn the water well over to you and your department.

This for your information and further handling.




RECEIVED
STATE CORPORATION COMMISSION
MAR 05 1984
3-5-84
CONSERVATION DIVISION
Wichita, Kansas

Oil/Gas Regulation and Water Protection



Joint Oil/Gas Regulatory Offices



STRICT 2
SUITE 202, CENTURY PLAZA BUILDING
W. DOUGLAS, WICHITA, KS. 67202
5) 265-3181

RALPH E. O'CONNOR, DISTRICT GEOLOGIST
WARREN KIRKPATRICK, FIELD SUPERVISOR
316-262-8330

February 13, 1984

Mr. S. Charles Pappageorge
Bell Brothers
Box 581, 201 North Jefferson
Robinson, Ill 62454

Dear Mr. Pappageorge:

On February 9, 1984, a routine inspection was made on your abandoned property on the Schwainger lease SE-NE-NW, Sec. 28-26-4W, Reno County, Kansas and the following irregularities were found.

On the well, there is now 115 feet of open hole from the surface to the top of the cement. This will need to be filled with cement to the surface.

The water well that was dug to service the drilling rig when the well was drilled will need the 6 inch steel casing pulled and filled with cement.

Where the tank battery was, there is a section of tank walk and several pieces of pipe and angle iron that needs to be cleaned up.

We expect a reply to this notice by March 1, 1984, as to a date this problem will be corrected so an agent from this office can be present when the work is completed.

Sincerely,

Warren Kirkpatrick
Supervisor

pa

COMPLIMENTS OF:

OLLER'S, INC.

P.O. BOX 61 • SPIVEY, KS. 67142

"Don't Holler - Call Oller"

RES. PHONE
(316) 532-2477
KINGMAN, KANS.

COMPLETE
MAGNETO AND HEAD
REPAIR SERVICE

• OFFICE PHONE •
(316) 785-4261
SPIVEY, KANS.

J. G. Pappageorge Gen. Supt.
Bell Brothers

Box 581,

201 N. Jefferson

Robinson, Ill. 62454

Abandoned oil well
N.W/4 Sec 28-26-4w

Reno Co.

John Hilger Lease

Check Plugging
Report

MOTOR GRADER
DUMP TRUCKS
ROUSTABOUTS
HOT OILER
DITCHER

WINCH TRUCKS
TANK TRUCKS
PAY LOADER
BACKHOE
DOZER