

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

FORM CP-4

WELL PLUGGING RECORD

Reno County, Sec. 28 Twp. 26 Rge. 4 (X) X (W)

Location as "NE/CNW&SW&" or footage from lines SE NW NE

Lease Owner A. Scott Ritchie

Lease Name HILGER Well No. 1

Office Address 412 Union Center Building, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 20 19 75

Application for plugging filed October 20 19 75

Application for plugging approved October 20 19 75


Plugging commenced October 20 19 75

Plugging completed October 20 19 75

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation Depth to top Bottom Total Depth of Well 4063 feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. The table is currently empty.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole full of heavy mud. Bottom plug @ 450' w/40 sacks cement thru drill pipe. Mud to 210' w/25 sacks cement thru drill pipe. Mud to 40' w/1/2 sack hull plug and 10 sacks cement. 2 sacks cement in rat hole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co.

Address Box 823, Great Bend, Kansas 67530

STATE OF KANSAS COUNTY OF BARTON ss.

Larry Curtis (employee of owner) or (owner/representative) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Larry Curtis

Box 823, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 22nd day of October 19 75

My commission expires April 11, 1978 Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

OCT 23 1975
10-23-75
CONSERVATION DIVISION
Wichita, Kansas

DRILLERS' WELL LOG

DATE COMMENCED: October 8, 1975
DATE COMPLETED: October 20, 1975

A. Scott Ritchie
HILGER # 1
SE NW NE of Sec 28-T26S-R4W
Reno County, Kansas

ELEVATION: 1469 K.S.

0 - 210'	Red Bed, Sand
210 - 2579'	Shale and Lime
2579 - 2584'	Shale
2584 - 2592'	Shale and Lime
2592 - 2608'	Lime
2608 - 2792'	Shale
2792 - 2822'	Brown Lime
2822 - 3311'	Lime
3311 - 3457'	Lime and Shale
3457 - 4024'	Sand
4024 - 4044'	Shale and Lime
4044 - 4063'	Chert
	RTD

FORMATION DATA

Hasbner	2579
Toronto	2592
Douglas	2608
Brown Lime	2792
Kansas City	2822
Base K.C.	3311
Cherokee	3457
Mississippi	3615
Kinderhook	3940
Misner	4024
Viola	4044
RTD	4063

SURFACE PIPE:
Set 210' of used 8 5/8" pipe
@ 210' w/175 sacks Common cement,
2% Gel, 3% cc.

AFFIDAVIT

STATE OF KANSAS }
COUNTY OF BARTON } ss.

Larry Curtis, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 22nd day of October, 1975.

Maisty M. Hagne
Notary Public

My Commission Expires: April 11, 1978

RECEIVED
STATE CONSERVATION COMMISSION

OCT 23 1975
10-23-75
CONSERVATION DIVISION
Wichita, Kansas