

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-155-21,055-0001

LEASE NAME Mellies # 1

WELL NUMBER 1

980' Ft. from S Section Line

1630' Ft. from E Section Line

SEC. 18 TWP. 26S RGE. 4W (E) or (W)

COUNTY Reno

Date Well Completed 4-14-86

Plugging Commenced 9-5-1986

Plugging Completed 9-6-1986

Yes

LEASE OPERATOR B & B Farm Industries, Inc.

ADDRESS Box 6; Liberal, Ks. 67901

PHONE# (316) 624-3767 OPERATORS LICENSE NO. 7314

Character of Well Gas - D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Wichita, Ks.

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Miss. Depth to Top 3566 Bottom 3572 T.D. 3704

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	8 5/8 Surface	133	sur.	8 5/8	133'	None
	4 1/2 Prod.	3660	prod.	4 1/2	3660'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

4 1/2 Casing Set to 3660' & cemented 275 sx/DV tool at 355' & cemented to

surface-- Plug Back with CIBP at 3592'-- Perforations 3566-3572

Dumped sand to 3400'-- Spotted 6 sacks cement with baler-- Filled w/mud

& water to 300'-- Cemented to surface with redimix-- Cut casing & Weld Cap.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gressel Corp. License No. _____

Address Haysville, Ks.

STATE OF Kansas COUNTY OF Sedgwick, ss.


Kevin Todd Allam 721-3555 (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Kevin Todd Allam

(Address) 103 Stony Point Wichita, KS 67212

SUBSCRIBED AND SWORN TO before me this 11 day of September, 19 86

My Commission Exp



Notary Public

9-15-86

SEP 15 1986