

MAGNOLIA PETROLEUM COMPANY

Log of
 M. Thome well #1 P. I.
 NE/c NE 1/4 Sec. 17-26S-4W
 Reno County, Kansas

PLUGGING STARTED: September 20, 1949
 PLUGGING COMPLETED: September 27, 1949
 BY: Rice County Pulling Company
 Lyons, Kansas

CASING RECORD:
 13" - 195' - cem. w/200 sacks
 None pulled.
 7" - 4008' - cem. w/450 sacks
 2884' pulled.

FORMATION	TOP	BOTTOM
Red rock & sand	0	75
Red rock	75	150
Shale	150	195
13" OD casing set		195
Shale & salt	195	715
Shale & lime	715	1260
Shale & shells	1260	1645
Shale	1645	1815
Shale & lime	1815	2015
Shale & shells	2015	2100
Shale & lime	2100	2160
Shale & shells	2160	2245
Shale & lime	2245	2525
Lime	2525	2570
Shale	2570	2580
Lime	2580	2590
Lime & shale	2590	2910
Lime	2910	3475
Shale	3475	3490
Lime	3490	3540
Shale	3540	3620
Top Chat	3620	
Chat	3620	3670
Chat & Lime	3670	3755
Lime	3755	3910
Shale & Shells	3910	3945
Shale	3945	4008
7" OD casing set		4008 SIM
Top Misener	3983	
Standardized		
Sylvan Shale	4008	4018 Cored
Viola lime	4018	4021
Total Depth SIM		4021

HISTORY OF COMPLETION:

Treated w/250 gallons of acid solution on August 28, 1937 through 2 1/2" tubing.
 Treated by Chemical Process Company. Used 28 bbls oil during treatment.
 Maximum pressure 1700#: After acid - 1134 bbls oil & no wtr.

PLUGGING RECORD: By Rice County Pulling Company - Lyons, Kansas

See Plugging Record.

RECEIVED
 Conservation
 OCT 18 1949 10-18-49
 STATE CORPORATION
 COMMISSION
 KANSAS