

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-155-21253-0000

LEASE NAME Diehl

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 25 TWP. 25 RGE. 10 (W)

COUNTY Reno

Date Well Completed

Plugging Commenced 3-20-96

Plugging Completed 3-22-96

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Sterling Oil Company, Inc.

ADDRESS 112 S. Broadway Sterling, Ks. 67579

PHONE#(316) 278-3727 OPERATORS LICENSE NO. 30108

Character of Well Oil

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Mike Wilson (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.O. 4020'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	220'	none
				5 1/2"	4007'	2750'

RECEIVED
STATE CORPORATION COMMISSION
MAR 26 1996
3-28-96

Describe in detail the manner in which the well was plugged, indicating where the mud was placed and the method or methods used in introducing it into the hole. If cement or other plugging material were used, state the character of same and depth placed, from feet to feet each sack of cement. Plugged off bottom with sand to 3844' dumped 5 sacks cement. Shot pipe at 3000', and at 2750'. Pulled up to 1450' pumped 35 sacks cement, pulled up to 900' pumped 35 sacks cement, pulled up to 270' circulated to surface with 90 sacks cement, pulled rest of casing, topped off with 10 sacks cement. 60/40 POZMIX 4% gel. Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 209 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Sterling Oil Company, Inc. -Sterling, Ks.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 209 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 26th day of March, 19 96

[Signature]
Notary Public

My Commission Expires:

