


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Reno County, Sec. 15 Twp 26 Rge. 5W (X) (W)
Location as "NE/CNW/SW" or footage from lines. C NW NE
Lease Owner Brad's Petroleum Co.
Lease Name White Well No. 1
Office Address 4040 N. Lincoln, Oklahoma City, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 12/4/68 19
Application for plugging filed 12/4/68 19
Application for plugging approved 12/4/68 19
Plugging commenced 12/4/68 19
Plugging completed 12/4/68 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Depth to top Bottom Total Depth of Well 4,300 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	242	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud to 600 ft. . . Plug @ 600 ft., 25 sacks cement
" " " 235 ft. . . Plug @ 235 ft., 25 " "
" " " 40 ft. . . Plug @ 40 ft., 10 " "

3 sacks cement in rat hole

RECEIVED
STATE CORPORATION COMMISSION

DEC 10 1968

CONSERVATION DIVISION
Wichita, Kansas

12-10-68

Name of Plugging Contractor
Address

(If additional description is necessary, use BACK of this sheet)
Graves Drilling Co., Inc.
505 Union Center

STATE OF Kansas

COUNTY OF Sedgwick, ss.

Mary Ann Scott, Graves (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

505 Union Center, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 9th day of December, 1968

My commission expires July 28, 1970

Mary Ann Scott

Notary Public.

ROTARY DRILLERS' LOG

OPERATOR: Brad's Petroleum Co.
4040 N. Lincoln
Oklahoma City, Okla. 73105

DRILLING COMMENCED: 11-25-68

CONTRACTOR: Graves Drilling Co., Inc.
505 Union Center
Wichita, Kansas 67202

DRILLING COMPLETED: 12-4-68

CASING RECORD: 242' of 8 5/8" casing,
cemented with 150 sacks

LOCATION: C NW NE
Sec. 31-26S-5W
Reno County, Kans.

0	-	28'	Soil
28	-	59'	Sandy shale
59	-	82'	Lime
82	-	196'	Shale
196	-	210'	Sandy shale
210	-	285'	Lime
285	-	810'	Shale and shells
810	-	1385"	Lime and shale
1385	-	1600'	Sandy lime
1600	-	1875'	Shale and shells
1875	-	2335'	Sandy shale
2335	-	2725'	Lime and shale
2725	-	2775'	Shale
2775	-	2930'	Sandy shale
2930	-	3434'	Lime
3434	-	3718'	Shale
3718	-	3965'	Lime
3965	-	4057'	Shale
4057	-	4082'	Sand
4082	-	4108'	Shale
4108	-	4160'	Lime
4160	-	4232'	Sandy shale
4232	-	4300'	Lime T.D.

RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1968
CONSERVATION DIVISION
Wichita, Kansas


12-10-68

I hereby certify that the foregoing statements are true and correct, to the best of my knowledge.

GRAVES DRILLING CO., INC.

By

John Graves
President



Subscribed and sworn to before me, a Notary Public, this 9th day of December, 1968.

My commission expires July 28, 1970

Mary Ann Scott
Mary Ann Scott, Notary Public