

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD
OR
FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

NORTH

***Locate well correctly on above
Section Plat**

Reno County, Sec. 20 Twp. 26 Rge. 5 (E) (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. C W $\frac{1}{2}$ NW $\frac{1}{4}$ SE $\frac{1}{4}$

Lease Owner The Dickey Oil Company

Lease Name.....Schwartz..... Well No..1.....

Office Address Wichita, Kansas.....

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date, well completed..... May 6 1942

Application for plugging filed..... May 6 1942

Application for plugging approved..... May 7 1942

Plugging Commenced.....19.....

Plugging Completed.....19.....

Reason for abandonment of well or producing formation.....Dry Hole.....

If a producing well is abandoned, date of last production.....19.....

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well. Mr. Ruel Durkee, McPherson, Kansas

Producing formation..... Depth to top..... Bottom..... Total Depth of Well 4190 Feet

Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Mud from 4190 to 175'; 10 sacks cement at 175'; mud from 175' to top of hole; 5 sacks cement at top of surface casing; welded steel plate over top of hole.



(If additional description is necessary, use **BACK** of this sheet)

Correspondence regarding this well should be addressed to.....The Dickey Oil Company

Address..... 713 Petroleum Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Wayne Bradley

(employee of owner) ~~XXXXXXXXXXXX~~

Wayne Bradley (employee of owner) ~~in~~ ^{for} owner or operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

713 Petroleum Building, Wichita, Kansas

SUBSCRIBED AND SWORN to before me this 18th day of MAY 1942 May, 1942.

/ My commission expires: Aug. 2, 1945.

My commission expires.....

Notary Public.

THE DICKEY OIL COMPANY
Schwartz Well No. 1

COMMENCED: 4/5/42
COMPLETED: 5/6/42

Casing Record

LOCATION: C-44 NW 1/4 SE 20-26-5
Reno County, Kansas

103'

10"

surface	15
sand	22
red bed	35
shale and shells	560
salt and shale	693
shale and shells	825
salt	850
lime and shale	865
broken lime	1700
shale and shells	1915
shale and lime	2280
lime	2460
shale and shells	2535
broken lime	2620
shale and shells	2810
sandy lime	2838
broken lime	2845
shale and shells	2891
top Lansing	2900
lime	3238
lime and shale	3267
lime	3337
lime and shale	3375
broken lime	3425
lime and shale	3480
broken lime	3512
lime and shale	3562
chat	3565
broken lime	3589
shale	3635
chat	3639
chat and lime	3691
chat	3722
chat and lime	3726
chat	3737
chat and lime	3839
lime	3848
chat and lime	3861
broken lime	3883
top Kinderhook	3890
shale and lime	3926
top Misner	4001
shale	4002
slight stain	4006 - 4012
sand	4023
sandy shale	4034
top Viola	4038
top Simpson	4078
top Arbuckle	4170
Arbuckle lime	4190
T. D.	4190

2800
5-16-42

