


15-035-00736-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
800 Biring Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plot

Cowley County, Sec. 10 Twp. 30S Rge. 5E (E) (W)
Location as "NE/CNW/SW" or footage from lines SW SW NW
Lease Owner McNeish & Galapp
Lease Name Kennedy Well No. 1
Office Address 528 State Bank Bldg., Winfield, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Sept. 29 19 55
Application for plugging filed Sept. 29 19 55
Application for plugging approved Sept. 29 19 55
Plugging commenced Sept. 29 19 55
Plugging completed Sept. 29 19 55
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. S. Lemaster
Producing formation Depth to top Bottom Total Depth of Well 2933 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged with mud from 2933 ft. to 230 ft.; cement from 230 ft. to 190 ft.; mud from 190 ft. to 40 ft.; cement from 40 ft. to 0 ft.

RECEIVED
STATE OF KANSAS
10-12-55
OCT 12 1955

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor
Address

STATE OF Kansas COUNTY OF Cowley ss.
Geo. T. McNeish, one of operators (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Geo. T. McNeish
528 State Bank Bldg., Winfield, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 4th day of October 19 55

My commission expires April 9, 1957 Grace Hill Notary Public.

PLUGGING
FILE SEC 10 T 30 R 5E
BOOK PAGE 4 LINE 25

15-035-00736-0000

WELL LOG

Company: McNeish & Gralapp
Winfield, Kansas

Farm: Kennedy #1
SW SW NW Sec. 10-30S-5E
Cowley County, Kans.

Contractor: Watson Drilling Company, Inc.
Winfield, Kansas.

Comm: 9-20-55
Comp: 9-29-55

Casing Record:
209 ft. of 8 5/8" surface csg.

WELL DRY & PLUGGED

Surface clay	0	195
lime	195	200
shale	200	294
lime & shale	294	1800
shale	1800	1890
shale & sand	1830	1890
sandy shale & lime	1890	2000
sand & shale	2000	2040
shale	2040	2241
lime K. C.	2241	2490
lime & shale	2490	2515
lime	2515	2555
shale	2555	2562
shale & lime	2562	2585
sandy lime shale	2585	2621
lime	2621	2683
lime & shale	2683	2870
sand	2870	2873
CORE #1	2873	2887
shale	2887	2910
Mississippi Lime	2910	2933

T. D. 2933 ft.

Plugged 9-29-55 Mud from 2933 ft. to 230 ft.;
cement from 230 ft. to 190 ft.; mud from 190 ft. to 40 ft.;
cement from 40 ft. to 0 ft.

PLUGGING
 FILE SEC 10-30S-5E
 BOOK PAGE 2 LINE 25