

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
30 S. Market, Room 207B  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-155-21264-0000

LEASE NAME Markhart

WELL NUMBER 1

710 Ft. from <sup>N</sup> Section Line

2030 Ft. from E. Section Line

SEC. 22 TWP. 25 RGE. 9W (E) or (W)

COUNTY Reno

Date Well Completed

Plugging Commenced 3-8-01

Plugging Completed 3-12-01

LEASE OPERATOR GLOBE OPERATING, INC.  
ADDRESS P.O. Box 12 Great Bend, Kansas 67530

PHONE (316) 792-7607 OPERATORS LICENSE NO. 6170

Character of Well GAS Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)  
by Jack Luthi (KCC District Agent's Name).

Is ACO-1 filled? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4256'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED  
STATE CORPORATION COMMISSION  
3-28-01  
MAR 20 2001

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	237'	None
				5-1/2"	4251'	2517'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each. Plugged off bottom with sand to 3450' and 5 sks. cement. Shot pipe @3000; 2700' and 2517'. Pulled pipe up to 1655', pumped 5 sks. gel, 200# hulls and 35 sks. cement. Pulled up to 800', pumped 35 sks. cement, pulled up to 300', pumped 130 sks. cement and circulated to surface. Pulled rest of pipe, surface stayed full. 60/40 pos. 4% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Globe Operating, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)  
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed; the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 16th day of March, 2001.

Irene Herzberg  
Notary Public

My Commission Expires:

