

STATE OF KANSAS
STATE CORPORATION COMMISSION
10 Colorado Derby Building
Topeka, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-155-21,172-0000

LEASE NAME Schmucker

WELL NUMBER 1

4620 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 29 TWP. 25 RGE. 9 (E or W)

COUNTY Reno

Date Well Completed 07-21-91

Plugging Commenced 07-21-91

Plugging Completed 07-21-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Wilcat Oil & Gas Inc.

ADDRESS P.O. Box 90 Lyons, KS 67554

PHONE#(316) 257-5587 OPERATORS LICENSE NO. 6153

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-16-91 (date)

Glen Ward (KCC District Agent's Name).

ACO-1 filed? to be filed by operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 3990

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
						<u>7-24-91</u>
						<u>JUL 24 1991</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Bottom Plug: @ 1500' w/35 sacks cement thru drill pipe
Next Plug: @ 1000' w/35 " " " " " " 10 sacks in Rat Hole
Next Plug: @ 225' w/35 " " " " " "
Top Plug: @ 60' w/25 " " " " " "

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address P.O. Box 823 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: _____

STATE OF Kansas COUNTY OF Barton, ss.

Leonard Williamson

(Employee of Operator) or ~~XXXXXXXXXX~~ of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Leonard Williamson

(Address) P.O. Box 823 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 23rd day of July, 19 91

Paula Ann Laudick
Notary Public

My Commission Expires: _____



DRILLER'S WELL LOG

DATE COMMENCED: July 15, 1991
DATE COMPLETED: July 21, 1991

Wildcat Oil & Gas, Inc.
SCHMUCKER #1
C N/2 NW
Sec. 29, T25S, R9W
Reno County, Ks.

ELEVATION: 1704 K.B.

- 0 - 550' Surface soil, Red Bad, Sand
- 550 - 572' Anhydrite
- 572 - 1220' Shale
- 1220 - 1720' Shale w/Lime Streaks
- 1720 - 2865' Lime & Shale
- 2865 - 3199' Lime
- 3199 - 3414' Shale & Lime
- 3414 - 3764' Lime
- 3764 - 3894' Shale & Lime
- 3894 - 3990' Chert & Lime
- 3990' RTD

Surface Pipe: Set new
8-5/8", 20# pipe @178'
w/140 sacks 60/40' pozmix
2% gel 3% cc.

AFFIDAVIT


STATE OF KANSAS
COUNTY OF BARTON) ss

Leonard Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 23rd day of July 1991.

Paula Ann Laudick
Notary Public



RECEIVED
STATE COMMISSION

JUL 24 1991