

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-155-21297-0000

LEASE NAME V. Kittle

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER #1

330 Ft. from S Section Line

2310 Ft. from E Section Line

LEASE OPERATOR CLINTON PRODUCTION, Inc.

ADDRESS 330 North Armour  
 Wichita, Kansas 67206

PHONE# (316) 684-7996 OPERATORS LICENSE NO. 5585

Character of Well D & A

(Oil, Gas, D&A SWD, Input, Water Supply Well)

SEC. 29 TWP. 25 SRGE. 9W (5) or (W)

COUNTY Reno

Date Well Completed 10-17-93  
10-16-93

Plugging Commenced 11:15 PM

Plugging Completed 10-17-93  
1:15 AM

The plugging proposal was approved on 10:00 AM, 10-13093 (date)

by Jerry Clark (KCC District Agent's Name).

Is ACO-1 filed?            If not, is well log attached? Yes

Producing Formation            Depth to Top            Bottom            T.O. 4015'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	225' KB	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each set.  
Filled hole with heavy mud, 35 sacks at 1340'; 35 sacks at 880'; 35 sacks at 275' and 25 sacks at 60'. Used 60/40 Pozmix, 4% gel. 15 sacks in rathole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor STERLING DRILLING COMPANY License No. 5142

Address P. O. Box 129  
 Sterling, Kansas 67579-0129

STATE OF KANSAS COUNTY OF RICE, ss.

Richard L. Mead (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Richard L. Mead  
 Richard L. Mead, Vice President

(Address) P. O. Box 129, Sterling, Kansas 67579-0129

SUBSCRIBED AND SWORN TO before me this 18th day of October, 19 93

Cheryl R. Davis  
 Cheryl R. Davis, Notary Public

My Commission Expires: 2-15-97



# STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

SAMPLE LOG ----- V. KITTLE #1

Located: SW SW SE. section 29-25S-9W, Reno County, Kansas

OWNER: Clinton Production, Inc.

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: October 11, 1993

COMPLETED: October 17, 1993

TOTAL DEPTH: 4015'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 38 Surface Soil and Sand	Ran 5 joints new 8 5/8", 20# casing.
38 - 230 Red Bed	213.43' pipe set at 225' K.B. Cemented
230 - 1400 Shales	with 185 sacks 60/40 Pozmix, 2% gel and
1400 - 4015 Lime and Shale	3% cc. Plug down at 4:00 PM, 10-11-93,
	by Allied.
	Plugged

Deviation Surveys:    1/2° at 230'  
                               1° at 3930'  
                               1 1/2° at 4015'

RECEIVED  
 STATE CORPORATION COMMISSION  
 11-5-93  
 NOV 05 1993  
 CONSERVATION DIVISION  
 Wichita, Kansas