


1-13-55

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Reno County, Sec. 9 Twp. 26S Rge. 8 ~~W~~ (W)
Location as "NE/CNW/SW" or footage from lines SW SW SW
Lease Owner Braden Drilling Company
Lease Name Cole Well No. 1
Office Address 814 Union National Bank Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry
Date well completed January 3, 1955 19
Application for plugging filed January 4, 1955 19
Application for plugging approved January 4, 1955 19
Plugging commenced January 4, 1955 19
Plugging completed January 7, 1955 19
Reason for abandonment of well or producing formation dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4401 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TD	SIZE	PUT IN	PULLED OUT
				8-5/8"	160'	none
				5 1/2"	3405'	3002'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with sand from 3400' to 3340' and ran 6 sacks of cement. Mudded hole to 155', set a 10' rock bridge and ran 15 sacks of cement. Mudded hole to 25', set a 10' rock bridge and ran 5 sacks of cement on top. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.
Address Chase, Kansas


STATE OF Kansas, COUNTY OF Sedgwick, ss.
Louis E. Potucek (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Louis E. Potucek
814 Union National Bank Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of January, 1955

Norma Risher
Notary Public.

My commission expires April 29, 1957



1-13-55
CONSERVATION DIVISION
Wichita, Kansas

COLE #1

1-13-55

Operator: Braden Drilling Company

SW SW SW
9-26S-8W
Reno County, Kansas

Contractor: Braden Drilling Company

Test Commenced: 11-30-54
Test Completed: 12-18-54

Elev: 1626 R.B.

Casing Record: Set 160' of 8-5/8" casing with 175 sacks cement.
Set 3405' of 5 1/2" casing, with 75 sacks pozmix cement.

Surface	15
Red Rock & shale	110
Red Rock	160
Red Rock & shells	270
Red Bed & shale	570
Shale & shells	1075
Anhydrite	1110
Shale & shells	1410
Lime & shale	2125
Shale & shells	2330
Shale & lime	2635
Shale, lime & shells	2785
Lime & shale	2949
Lime	3060
Lime & shale	3202
Sand, shale & lime	3284
Lime	3376
Lime & shale	3445
Lime	3862
Lime & shale	3887
Mississippi	3960
Miss. lime	3966
Lime	3980
Miss. chat	4015
Lime	4025
Lime & shale	4120
Shale	4210
Viola lime	4220
Lime	4275
Simpson	4279
Lime	4401 T. D. R. B.

STATE OF KANSAS,
(SS:-
SEDCWICK COUNTY,)

I hereby certify that the above information is true and correct as revealed by the records of the Braden Drilling Company.

Harold Patrick

Subscribed and sworn to before me this 22nd day of December, 1954.

Norma Rieberg
Notary Public

My commission expires April 29, 1957.

