

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

2-13-64

NORTH



Locate well correctly on above
Section Plat

Reno County. Sec. 9 Twp. 26 Rge. 8 (W)

Location as "NE/CNW4SW4" or footage from lines C NW NW

Lease Owner Fred B. Anschutz

Lease Name Kelman

Well No. 1

Office Address 1521 Wichita Plaza, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed 2-8 19 64

Application for plugging filed 2-8 19 64

Application for plugging approved 2-8 19 64

Plugging commenced 2-8 19 64

Plugging completed 2-8 19 64

Reason for abandonment of well or producing formation None

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Towman

Producing formation Depth to top Bottom Total Depth of Well 3330 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	124	8 5/8	128	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with wood chips to 180',
 $\frac{1}{2}$ sk hulls, plug 40 sks cement. Plug,
 $\frac{1}{2}$ sk hulls, 10 sks cement. 2 sks
 cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

FEB 13 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Terrel Drilling and Producing

Address Russell, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.

Joe K. Branum (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Box 606, Russell, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of February, 19 64

My commission expires 12-12-66

Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

FEB 13 1964

2-13-64

CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

OPERATOR: Fred B. Anschutz
1521 Wichita Plaza
Wichita, Kansas

CONTRACTOR: Terrel Drilling & Producing
Box 606
Russell, Kansas

LEASE: Kelman #1

COMMENCED: January 29, 1964

LOCATION: C NW NW 9-26-8W
Reno County, Kansas

COMPLETED: February 8, 1964

DEPTHS & LOCATIONS

Surface Clay & Sand	40	Shale	2050
Red Bed	300	Shale & Lime	2135
Shale & Shells	1040	Shale, Lime & Sand	2385
Anhydrite	1080	Shale, Sandy Lime	2430
Shale, Gyp & Salt	1250	Shale & Lime	2664
Salt Shale & Lime Shells	1420	Lime	2750
Shale & Lime Shells	1465	Shale & Lime	2810
Shale	1645	Lime & Shale	3056
Shale & Lime Streaks	1741	Shale & Sand	3255
Shale & Lime	1915	Lime (R.T.D.)	3330

STATE OF KANSAS)

COUNTY OF RUSSELL) ss...

Joe K. Branum, owner of Terrel Drilling and Producing, being first duly sworn on oath says: "That I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct."


Joe K. Branum - TERREL DRILLING & PRODUCING

Subscribed and sworn before me this 12th day of February, 1964.

Notary Public

My Commission expires December 12, 1966