

15-155-30084-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Reno County. Sec. 2 Twp. 24 Rge. 5 (E) (W) X
Location as "NE/CNW/SW" or footage from lines NE/4 SW/4 NE/4

Lease Owner Brunson-Spines

Lease Name Rayl Well No. 2

Office Address 800 Wichita Plaza, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Not complete

Date well completed _____ 19__

Application for plugging filed _____ 19__

Application for plugging approved _____ 19__

Plugging commenced _____ 19__

Plugging completed September 25, 19 65

Reason for abandonment of well or producing formation
Moved location

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert J. Toman, Holyrood, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Clay		0ft	20			
Sand		20	155			
Shale		155	191	13"	191 ft.	None
Shale & Salt		191	500			
Salt & Shale		500	600			
Anhydrite		600	693	8 5/8"	693 ft.	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole Dry and abandoned. Set bottom plug at 265 ft.
Plugged with Halliburton plug and rock and cemented with 25 sacks cement. Filled hole with mud to 40 ft. and set Halliburton plug and 1/2 sack of hulls and cemented with 10 sacks cement. Plugging completed at 2:00 P.M.

RECEIVED
STATE CORPORATION COMMISSION

OCT 8 1965
10-8-65
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Blackstone Drilling, Inc.

Address Box # 455, McPherson, Kansas 67460

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
W. S. Rick Brunson (operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) W.S. Brunson

800 Wichita Plaza, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of September, 19 65

My commission expires June 9, 1969

Pearl E. Craytor
Pearl E. Craytor
Notary Public.



Blackstone Drilling, Inc.

Box 455 523 West Kansas Phone CH 1-1250

McPHERSON KANSAS
67460

SEP 29 1965

September 28, 1965

COMPANY: BRUNSON-SPINES
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: RAYL # 2
 LOCATION: NE/4 SW/4 NE/4, Sec. 2-24-5
 Reno County, Kansas
 COMMENCED: September 17, 1965
 COMPLETED: September 24, 1965
 ELEVATION: 1497 K.B.

0	to	20	Clay
20	to	155	Sand
155	to	191	Shale
191	to	500	Shale & Salt
500	to	600	Salt & Shale
600	to	693	Anhydrite
693	to	1050	Shale & Lime
1050	to	150	Lime
1250	to	1376	Lime & Shale
		1376	T. D.

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 8 1965
 CONSERVATION DIVISION
 Wichita, Kansas

Cut 17 1/4 in. hole to 191 ft. and run 194 ft. of 13 in. surface pipe and cemented with 250 sacks cement. Plug down at 12:30 A.M., September 17, 1965. Pipe set on bottom at 191 ft...Cut 12 1/4 in. hole to 693 ft. and run 693 ft. of 8 5/8 in. surface casing and cemented with 300 sacks cement. Plug down at 4:30 P.M., September 22, 1965. Cut 7 7/8 in. hole to 1376 ft. Made bit trip at 1376 ft. Pipe stopped at 670 ft. going in hole - tried to get in surface pipe with new bit. Reamed pipe from 420 ft. to 440 ft. Reamed pipe from 640 ft. to 654 ft. Decided to abandon hole. Set bottom plug at 265 ft. Plugged with Halliburton plug and rock. Cemented with 25 sacks cement and filled hole with mud to 40 ft. and set Halliburton plug and 1/2 sack of hulls and cemented with 10 sacks cement. Plugging completed at 2:00 P.M. by Gilbert J. Toman, State Plugger, Holyrood, Kansas.

TOPS: Anhydrite - 600'

Measurements taken from K. B.

CERTIFICATE

I, H. J. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Rayl #2, located on the NE/4 SW/4 NE/4 of Sec. 2-24-5, Reno County, Kansas as reflected by the files of Blackstone Drilling, Inc.

H. J. Plouffe
 H. J. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 28th day of September, 1965.

Ruth McVay
 Ruth McVay - Notary Public

My Commission Expires: December 18, 1965