

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAY 16 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Frank Musgrove of Hellar Drilling Company has this date requested permission to plug the following described well:

Mr. Musgrove guarantees payment of the plugging fee.

Operator's full Name: Hellar Drilling Company, Inc.

Complete Address: 1014 Union Center Bldg., Wichita, Kansas

Lease Name: Halley "B" Well No. # 1

Location: NE NW NW Sec. 3 Twp. 25 Rge. 13 (E)(W) W

County Stafford Total Depth 4246' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Musgrove was instructed to plug the well as follows:

253' of 8 5/8" surface pipe, cement circulated with 250 sackss.
Fill hole with drilling mud to 240', 1st cementing plug, bridge
with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with
drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of
hulls, and cement with 10 sacks to base of cellar. Bridge and
cement rat hole with 2 sacks.

Very truly yours,

Aulie Ewing
Conservation Division Agent