

State of Kansas



FORM - CP-2

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAY 25 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Paul Lacey of Beardmore Drilling Co. has this date requested permission to plug the following described well:

Mr. Lacey guarantees payment of the plugging fee.

Operator's full Name: Beardmore Drilling Company

Complete Address: 827 Beacon Bldg., Wichita, Kansas

Lease Name: Cornwell Well No. # 1

Location: NE NW SW Sec. 4 Twp. 25 Rge. 13 (E) (W) W

County Stafford Total Depth 4025 Oil Well         

Gas Well          Input Well          SWD Well          D & A X Lost Hole         

Mr. Lacey was instructed to plug the well as follows:

358' of 8 5/8" surface pipe, cemented with 275 sacks. Fill hole with drilling mud to 275', 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent