

State of Kansas



JOHN ANDERSON, Jr. Governor  
 WILLIAM L MITCHELL, Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND D. HARVEY Secretary  
 ROBT. C. LONDERHOLM Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

May 27, 1965 RECEIVED  
 STATE CORPORATION COMMISSION

JUN 1 1965

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita 2, Kansas

Dear Sir:

Mr. Harold Boyd of A. L Jackson Drlg. Co. has this  
 date requested permission to plug the following described well:

Mr. Boyd guarantees payment of the plugging fee.

Operator's full Name: E. H. Riggs

Complete Address: 1107 Union Nat'l Bldg., Wichita, Kansas

Lease Name: Kimes Well No. 1

Location: C SW NE Sec. 15 Twp. 25 Rgs. 8 (E) (W) X

County Reno Total Depth 4255' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Boyd was instructed to plug the well as follows:

Fill hole with mud to 240'. Push plug and  $\frac{1}{4}$  sack hulls to  
240' and cement hole with 25 sacks through drill pipe.

Fill hole with mud to 40'. Push plug and  $\frac{1}{2}$  sack hulls to  
40' and cap hole with 10 sacks cement.

Bridge rathole, and cement with 2 sacks.

Very truly yours,

Conservation Division Agent