

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

July 22, 1969

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 14 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Owen Bailey of Santa Fe Pipe & Supply Co. has this date requested permission to plug the following described well:

Mr. Bailey guarantees payment of the plugging fee.

Operator's full Name: Ray Maxwell

Complete Address: 2150 E. Douglas, Wichita, Kansas 67208

Lease Name: Krehbiel Well No. 1

Location: C NE NE Sec. 23 Twp. 25 Rge. 8 (E)(W) X

County: Reno Total Depth 4137' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Bailey was instructed to plug the well as follows:

Push 5 1/2" plug to 3500'. Fill hole with sand to 3490' and cement with
5 sacks cement. Fill hole with mud to 240'. Set rock bridge from 240'
to 230' and cement hole with 25 sacks cement. Fill hole with mud to 40'.
Set rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,


 Conservation Division Agent