

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

June 14, 1974

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)
 RECEIVED
STATE CORPORATION COMMISSION
JUN 20 1974
CONSERVATION DIVISION
Wichita, Kansas

6-20-74

 J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

 Mr. Herbert French of Pickrell Drilling Co. has this
date requested permission to plug the following described well:

 Mr. French guarantees payment of the plugging fee.

 Operator's full Name: Pickrell Drilling Company

 Complete Address: 705 Fourth Nat'l Bank Bldg., Wichita, Kansas 67202

 Lease Name: Sitton "A" Well No. 1

 Location: SE SE Sec. 22 Twp. 25 Rge. 8 (E) (W) X

 County: Reno Total Depth 4159' Oil Well

 Gas Well Input Well SWD Well D & A X Lost Hole

 Mr. French was instructed to plug the well as follows:

Fill hole with mud. Push plug to 400' and pump 40 sacks
cement through drill pipe at 400'. Pump 20 sacks cement
through drill pipe at 200'. Push plug and 1/2 sack hulls to
40' and cap hole with 10 sacks cement. Bridge rathole and
cement with 2 sacks cement.

Very truly yours,

Conservation Division Agent