



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS
 JEWEL M. OGDEN, Director

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JUL 27 1962

CONSERVATION DIVISION
 Wichita, Kansas

7-27-62

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date July 18, 1962, 1961, authorized the following plugging operation:

Operator's full Name: Lario Oil & Gas Co.

Complete Address: 301 S. Market, Wichita, Kansas.

Lease Name: Hornbaker Well No. 7.

Location: SE NE NE Sec. 29 Twp. 25 Rge. 6 (E)(W)

County: Reno. Total Depth: 4105'

Oil Well Gas Well Input Well SWD Well

D & A Other well as hereafter indicated:

Abanded oilwell.

Operator was instructed to plug well as follows:

~~5 1/2" pipe set at 4104' with 150 sacks cement circulated. Prefer-
 ation from 3992' to 3998' Hole sanded to 3980' and 5 sacks
 cement. 296' of 8 5/8" surface pipe circulated with 150 sacks
 cement. Hole filled with mud to 200' 10' Rock bridge and 20 sacks
 cement. hole filled with mud to 40', rock bridge (10') and
 10 sacks cement to bottom of cellar.~~

Very truly yours,

Herman Gustus

