

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

November 18, 1969

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 26 1969
CONSERVATION DIVISION
Wichita, Kansas

11-26-69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Jim Beakey of Forbes Casing Pulling Inc. has this date requested permission to plug the following described well:

Mr. Beakey guarantees payment of the plugging fee.

Operator's full Name: Mid-Continent Marine Drilling, Inc.

Complete Address: Box 191, Mc Pherson, Kansas 67460

Lease Name: N. Hilger Unit Well No. 2

Location: NE NE SE Sec. 33 Twp. 25 Rge. 4 (W) X

County: Reno Total Depth 4129' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Beakey was instructed to plug the well as follows:

Push 7" plug to 4090'. Fill hole with sand to 4080' and cement with
6 sacks cement. Fill hole with mud to 197'. Set rock bridge from 197'
to 185' and cement hole to base of cellar with 4 yards ready mix concrete.

Very truly yours,

William J. Lawrence
Conservation Division Agent