

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 16 1966  
CONSERVATION DIVISION  
Wichita, Kansas

11-16-66

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Bill Nelson of Walters Drilling Company has this date requested permission to plug the following described well:

Mr. Nelson guarantees payment of the plugging fee.

Operator's full Name: Walters Drilling Co. & Oil Property Management, Inc.

Complete Address: 400 Insurance Bldg., Wichita, Kansas

Lease Name: Thacher Well No. # 1

Location: SW SW SW Sec. 34 Twp. 25 Rge. 11 (E)(W) W

County Stafford Total Depth 4400' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Nelson was instructed to plug the well as follows:

248' of 8 5/8" surface pipe, cement circulated with 200 sacks. Fill hole with drilling mud to 230', 1st cementing plug, bridge with  $\frac{1}{2}$  sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with  $\frac{1}{2}$  sack of hulls, and cement with 10 sacks to base of the cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent