



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

NOV 15 1963

CONSERVATION DIVISION  
Wichita, Kansas

11-15-63

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Copeland of Western Petroleum Co. Inc has this date requested permission to plug the following described well:

Mr. Copeland guarantees payment of the plugging fee.

Operator's full Name: Continental Oil Co.

Complete Address: Box 267, Great Bend, Kansas

Lease Name: Riley Well No. # 1

Location: SE SE SE Sec. 32 Twp. 25 Rge. 11 (E) (W) W

County Stafford Total Depth 4350 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Copeland was instructed to plug the well as follows:

10 3/4"  
250' of ~~XXXXX~~ surface pipe, cemented with 300 sacks.

Fill hole with drilling mud to 250', 1st cementing plug,  
1/2 sack hulls, cement with 30 sacks. Fill hole with drill-  
ing mud to 40', 1/2 sack hulls, cement with 15 sacks to  
base cellar, Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent