

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 1 1985  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Vaughn Francis of Terrel Drilling & Prod. has this  
date requested permission to plug the following described well:

3-1-85

Mr. Francis guarantees payment of the plugging fee.

Operator's full Name: Robert L. Jones & R. D. Olson

Complete Address: 353 North Armour, Wichita, Kansas

Lease Name: McCune Well No. # 1

Location: C SW NW Sec. 10 Twp. 25 Rgs. 11 (E) (W) W

County Stafford Total Depth 3550' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Francis was instructed to plug the well as follows:

263' of 8 5/8" surface pipe, cement circulated. Fill hole  
with drilling mud to 240', 1st cementing plug, bridge with  
hulls, and cement with 25 sacks. Fill hole with drilling  
mud to 40', 2nd cementing plug, bridge with hulls, and cement  
with 10 sacks to base of cellar. Bridge and cement rat hole  
with 2 sacks.

Very truly yours,

Aubie Elving  
Conservation Division Agent