

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
AUG 12 1965
8-12-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Stickle Drilling Company

Complete Address: 1100 Bitting Bldg., Wichita, Kansas

Lease Name O'Dell Well No. # 1

Location NE NE SW Sec. 8 Twp. 25 Rge. 13 (E) (W) W

County Stafford Total Depth 4324'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Stickle Drilling Company

Address: 1100 Bitting Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 11:00 PM Day 9th Month August Year 1965

The Above well was plugged as follows:

324' of 8 5/8" surface pipe, cement circulated with 300 sacks. Hole was
filled with drilling mud to 300', 1st cementing plug, bridged solid with
dry cement and hulls on fluid at 300', and cemented with 25 sacks. Hole
was filled with drilling mud to 40', 2nd cementing plug, bridged solid
with dry cement and hulls on fluid at 40', and cemented with 10 sacks to
the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 8-12-65

INV. NO. 1622-W