

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. CN/2 N/2 SW

LOCATION ~~SW-22W~~

SEC. 12 TWP. 14 RGE. 13-W

Dry Hole Abandoned Oil Well Abandoned Gas Well

I have today completed supervision of plugging of:

Well No. 1 Lease M. N. Fair

Operator Continental Oil Co. Address #207 Piteo Bldg. Wichita-Kans.

Field _____ County Stafford

Total Depth 4162 Feet.

(Describe briefly the manner in which the well was plugged)

*Surface Pipe 10 3/4 - 441 ft Circulated with cement.
9' casing set at 4152 ft. Cemented with 300 sacks cement.
Plugged back to 3736 ft with mud - four Wells Plug
& 6 Sacks of cement on top of Plug - Top of cement 3720 ft.
Ripped off & pulled the 9' casing - Mud to 250 ft.
Set Rock Bridge & 20 sacks of cement at 250 ft
Mud to 25 ft - R. Bridge & 5 sacks of cement
at the surface*

RECEIVED
STATE CORPORATION COMMISSION

DEC 15 1950

CONSERVATION DIVISION

C. W. [Signature]
District Conservation Agent

Date 12-12-50

PLUGGING
FILE SEC. 18785 R13W
BOOK PAGE 49 LINE 16

F