

R

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

Form CP-3

Rev. 6-1-68

RECEIVED
STATE CORPORATION COMMISSION

FEB 17 1977 2-17-77

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Continental Oil Co.
Complete Address 3535 NW 88th St. Oklahoma City, OKla
Lease Name South Leesberg Unit Well No. 205
Location C 14 1/2 NE Sec. 13 Twp. 25 Rge. 13 (E) (W)
County Stafford Total Depth 4131

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Nicholas Casing Pulling
Address Box 373 Conover, Kans License No. 711

Operation Completed: Hour 3:15 PM Day 15 Month Feb Year 1977

The above well was plugged as follows:

319' of 8 5/8 Surface Cemented with 150 SKs, 4131' of
5 1/2 Casing String Cemented with 200 SKs, Top Perf 3719
Cast Iron Bridge Plug Set at 3600, 1, 5K Cement, 5, SK Cement
with bailer, Recovered 2420' of 5 1/2, Pumped 3, 5Ks
Halls, 20, SKs Gel. Released Plug, 100 SKs Cement
with 4% Gel to Surface

Pumped by Swan Cementing Co

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: J. A. [Signature]
Well Plugging Supervisor

DATE 2-17-77

INV. NO. 4648-W