

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

JAN 8 1965
1-8-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Continental Oil Company

Complete Address: Box 267, Great Bend, Kansas

Lease Name Leesburg South Unit Well No. # 302

Location NW NE SE Sec. 13 Twp. 25 Rge. 13 (E) (W)

County Stafford Total Depth 4408

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated:

Plugging Contractor: Continental Oil Company and Globe Cementing Company

Address: Box 267, Great Bend, Kansas License No.

Operation Completed: Hour 11:00 PM Day 5th Month Jan. Year 1965

The Above well was plugged as follows:

280' of 10 3/4" surface pipe, cemented with 225 sacks. 4408' of 7" long
string. Top perforation 4225'. 7" hole had filled with Iron Sulfate to
900', where it would not take no more water on gravity, and it took 40
lbs. pressure to pump in to it. This 7" pipe was cut off below the 10 3/4"
surface pipe, and the hole was squeezed with 10 sacks of Gel-Mud and 125
sacks of cement, through a 10 3/4" swage. After cement had set up, swage
was taken off, and a wire line run in the hole to find the top of cement.
Cement was at 72' in the 7", and at 72' in the 10 3/4" surface pipe. Hole
was filled with Ready-Mix, to a mixture of 30 sacks of cement and water,
and was filled to the base of the cellar. No pipe was recovered from the
hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 1-8-65

INV. NO. 492-W

~~INVOICED~~
~~DATE~~
~~INV. NO.~~