

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasIntent to Drill, filed
February 15, 1967.RECEIVED
STATE CORPORATION COMMISSION
FEB 27 1967
2-27-67
CONSERVATION DIVISION
Wichita, KansasOperator's Full Name Rains & Williamson Oil Company, Inc.Complete Address: 1425 Wichita Plaza Bldg., Wichita, KansasLease Name Harry Russell Well No. # 1Location W/2 SW NW Sec. 14 Twp. 25 Rge. 13 (E) (W) WCounty Stafford Total Depth 4291'Abandoned Oil Well Gas Well Input Well SWD Well D & A X Other well as hereafter indicated: Plugging Contractor: Rains & Williamson Oil Company, Inc.Address: 1425 Wichita Plaza, Wichita, Kansas License No. Operation Completed: Hour 3:15PM Day 26th Month Feb. Year 1967

The Above well was plugged as follows:

309' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fluid
level in the hole was at 91'. 1st cementing plug and 1/2 sack of hulls
was pushed in fluid to 260', and cemented with 25 sacks, through the
drill pipe at 260'. Hole was filled with drilling mud to 40'. 2nd cem-
enting plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on
fluid at 40', and cemented with 9 sacks to the base of the cellar.
Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 2/27/67
INV. NO. 4827-WSigned: Archie Elving
Well Plugging Supervisor