

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
APR 21 1980
CONSERVATION DIVISIONS
Wichita, Kansas
CORPORATION COMMISSION

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 185 - 20,904 - 0000 (of this well)

4-21-80

Operator's Full Name Ralph G. Bowen.

Complete Address 4103 Panorama, Hutchinson, Ks. 67501

Lease Name Russell Well No. 1

Location NE SE SE Sec. 14 Twp 25s Rge. 13 (E) (W) X

County Stafford Total Depth 4281

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling.

Address Box 176 Chase, Ks. 67524 License No. 683

Operation Completed: Hour 3:15 Pm. Day 17 Month 4 Year 1980

The above well was plugged as follows:

225' 8 5/8" casing w/150 sax cement. 5 1/2" casing set at 4280' w/100
sax cement. Plug back to 3823'-Preforated from 3785' to 90'-Sand
back to 3750'-Top sand w/5 sax mixed cement w/ dump bailer. Pull
1965' casing-Allied mixed & pumped in 8 5/8" casing 8 sax hulls 25
sax gel-125 sax 50/50 posmix cement w/4% gel & 3% cc to top of csng.
Shut in w/400# pressure

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 4-21-80

INV. NO. 1967-w