

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 12 1964

CONSERVATION DIVISION
Wichita, Kansas

5-12-64

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Santa Fe Pipe & Supply

Complete Address: P. O. Box 562, Great Bend, Kansas

Lease Name G. Russell Well No. #. 1

Location S/2 S/2 SW Sec. 14 Twp. 25 Rge. 13 (E) (W) W

County Stafford Total Depth 4317

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Ace Pipe Pulling Company

Address: Box 304, Great Bend, Kansas License No. 2

Operation Completed: Hour 10:30AM Day 11th Month May Year 1964

The Above well was plugged as follows:

228' of 8 5/8" surface pipe, cement circulated. 4317' of 5 1/2" long string,
cemented with 100 sacks. Top perferation 4210'. Bottom of the hole was
sanded to 4200', and cemented with 5 sacks. Fluid level was up in the hole.
Plug was pushed to 225', with 10' of rock bridge. 12 sacks of cement was
mixed in a barrel and put on plug, through dump bailer, and let set over-
night. Next morning hole bailed down, and 13 sacks of cement was added to
the plug. Hole was filled with mud to 40', with 10' of rock bridge, and
cemented with 10 sacks to base cellar. 3400' of 5 1/2" long string was recov-
ered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/12/64

INV. NO. 9129-W

Signed: Archie Elving
Well Plugging Supervisor