

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
AUG 14 1969
CONSERVATION DIVISION
Wichita, Kansas

8-14-69

Operator's Full Name Ray Maxwell

Complete Address 2150 E. Douglas, Wichita, Kansas 67208

Lease Name Krehbiel Well No. 1

Location C NE NE Sec. 23 Twp. 25 Rge. 8 (E) (W) X

County Reno Total Depth 4137'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Santa Fe Pipe and Supply Inc.

Address Box 562, Great Bend, Kansas License No. 574

Operation Completed: Hour 2 PM Day 6 Month August Year 1969

The above well was plugged as follows:

5½" plug pushed to 3500'. Hole filled with sand to 3490' and cemented with 5 sacks
cement. Hole filled with mud to 240'. Rock bridge set from 240' to 230' and hole
cemented with 25 sacks cement. Hole filled with mud to 40'. Rock bridge set from
40' to 30' and hole cemented to base of cellar with 10 sacks cement.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED
DATE 8/14/69
INV. NO. 294-W