

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED

STATE CORPORATION COMMISSION

JUN 18 1969

CONSERVATION DIVISION
Wichita, Kansas

6-18-69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Woodman & Iannitti

Complete Address 706 Union Nat'l Bldg., Wichita, Kansas 67202

Lease Name Layman Well No. 1

Location C SE SE Sec. 23 Twp. 25 Rge. 8 (E) X (W) X

County Reno Total Depth 4095'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Operator

Address License No.

Operation Completed: Hour 2:45 AM Day 14 Month June Year 1969

The above well was plugged as follows:

Hole filled with mud to 245'. Plug and 1/4 sack hulls pushed to 245' and hole cemented
with 25 sacks cement through drill pipe. Hole filled with mud to 40'. Plug and 1/2
sacks hulls pushed to 40' and hole cemented to base of cellar with 10 sacks cement.
Rathole bridged and cemented with 2 sacks cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/18/69

INV. NO. 9961-11

Signed: [Signature]
Well Plugging Supervisor