

AFFIDAVIT AND COMPLETION FORM

ACO-1

This form must be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within five days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Please type. Complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316) 263-3238.


OPERATOR Wayne Walcher API NO. 15 - 185 - 21, 529-0000  
 ADDRESS 701 Bitting Building COUNTY Stafford  
Wichita, Kansas 67202 FIELD unknown  
 \*\*CONTACT PERSON Wayne Walcher LEASE Helmke  
 PHONE 316 267 1611

PURCHASER \_\_\_\_\_ WELL NO. #1  
 ADDRESS \_\_\_\_\_ WELL LOCATION SW SW NE  
 \_\_\_\_\_ Ft. from \_\_\_\_\_ Line and  
 \_\_\_\_\_ Ft. from \_\_\_\_\_ Line of  
 the SEC. 36 TWP. 25S RGE. 13W

DRILLING CONTRACTOR Big Springs Drilling, Inc.  
 ADDRESS P. O. Box 8287 - Munger Station  
Wichita, Kansas 67208

PLUGGING CONTRACTOR Service Company  
 ADDRESS Russell, Kansas

TOTAL DEPTH 4385' PBD  
 SPUD DATE 2-27-82 DATE COMPLETED 3-7-82  
 ELEV: GR1894 DF KB 1899



WELL PLAT  
 (Quarter) or (Full) Section - Please indicate.

KCC ✓  
 KGS ✓

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS  
 Report of all strings set — surface, intermediate, production, etc. (New) (Used) casing.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	20#	344'	Common	275 SX	2% gel 3% ccl

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD		
Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD  
 Amount and kind of material used

RECEIVED  
 STATE CORPORATION COMMISSION  
 3-18-82  
 MAR 18 1982  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

TEST DATE:		PRODUCTION	
Date of first production	Producing method (flowing, pumping, gas lift, etc.)	A.P.I. Gravity	
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF	Water bbls.
Disposition of gas (vented, used on lease or sold)		Producing interval (s)	

\*\* The person who can be reached by phone regarding any questions concerning this information.  
 A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

Name of lowest fresh water producing stratum Sand Depth 80'  
 Estimated height of cement behind pipe Circulation

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<u>DRILLERS LOG</u>				
Shale	0	756'		
Anhydrite	756'	781'		
Shale & Shells	781'	1593'		
Shale & Lime	1593'	4029'		
Lime	4029'	4285'		
Lime & Shale	4285'	4385'		
RTD	4385'			
 <u>SAMPLE TOPS:</u>				
Heebner	3495			
Brown Lime	3661			
Lansing (no shows)	3688			
BKC	3986			
Mississippian (poss. vssg)	4122			
DST #1 4130-50 30, 30, 30, 30				
Weak blow, died on 2nd opn'g,				
recov. 15' mud, no shows.				
IFP 20 - 20#				
ICIP 772#				
FFP 20 -20#				
FCIP 298#				
112 degrees				
Viola (no shows)	4180			
Simpson (no shows)	4276			
Arbuckle (no shows)	4367			
RTD	4385			
No mechanical log run				
Dry & Abandoned				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.


A F F I D A V I T

STATE OF Kansas, COUNTY OF Sedgwick SS,

Wayne Walcher OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH, DEPOSES AND SAYS:

THAT HE IS Wayne Walcher ~~FOR~~ owner and OPERATOR OF THE Helmke LEASE, AND IS DULY AUTHORIZED TO MAKE THIS AFFIDAVIT FOR AND ON BEHALF OF SAID OPERATOR, THAT WELL NO. 1 ON SAID LEASE HAS BEEN COMPLETED AS OF THE 7th DAY OF March 19 82, AND THAT ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.



(S) Wayne E. Walcher

SUBSCRIBED AND SWORN TO BEFORE ME THIS 15th DAY OF March 19 82

J. Ann Carrell  
 NOTARY PUBLIC

MY COMMISSION EXPIRES: January 22, 1986