

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 5403 EXPIRATION DATE 6-30-83

OPERATOR Wayne Walcher APT NO. 15-185-21,687-0000

ADDRESS 701 Bitting Building COUNTY Stafford

Wichita, KS 67202 FIELD

** CONTACT PERSON Wayne Walcher PHONE (316) 267-1611 PROD. FORMATION

PURCHASER LEASE Helmke

ADDRESS WELL NO. 2

DRILLING Red Tiger Drilling Company 990 Ft. from South Line and

CONTRACTOR 1720 KSB & T Building 990 Ft. from East Line of

ADDRESS Wichita, KS 67202 the NE (Qtr.) SEC36 TWP25S RGE 13W.

PLUGGING Allied Cementing Company WELL PLAT (Office Use Only)

CONTRACTOR Box 31, 332 W. Wichita KCC

ADDRESS Russell, KS 67665 KGS

TOTAL DEPTH 4230' PBDT SWD/REP

SPUD DATE 10-19-82 DATE COMPLETED 10-29-82 PLG.

ELEV: GR 1892 DF 1894 KB 1897

DRILLED WITH (ROTARY) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE

Amount of surface pipe set and cemented 375.64' DV Tool Used?

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO. Other

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

AFFIDAVIT

Wayne Walcher, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

Wayne Walcher (Name)

SUBSCRIBED AND SWORN TO BEFORE ME this 9th day of November

19 82.

Notary Public (Signature)

MY COMMISSION EXPIRES: 5-20-86

** The person who can be reached by phone information.

Wayne Walcher 316/267-1611

NOV 17 1982 CONSERVATION DIVISION Wichita Kansas

11-17-82



FILL IN WELL LOG AS REQUIRED:

FORMATION DESCRIPTION, CONTENTS, ETC.			TOP	BOTTOM	NAME	DEPTH
Sand & Clay			0	276	Anhydrite	723 to 748
Surface			276	385	Heebner	3473
Shale			385	485	Brown Lime	3638
Sand & Shale			485	723	Lansing	3662
Anhydrite			723	748	Base K. C.	3959
Shale			748	1080	Miss.	4097
Sand & Shale			1080	1715	Misener	4128
Shale			1715	2489	Viola	4132
Lime & Shale			2489	3015	Simpson Fm.	4205
Lime			3015	3378	" Sand	4212 to 21
Lime & Shale			3378	3552	Rot. TD	4230
Lime			3552	3668	No mechanical log run.	
Lime & Shale			3668	3679	D & A	
Lime			3679	3864		
Lime & Shale			3864	3918		
Lime			3918	4230		
RTD				4230		
<p>DST #1 4100 4124 30, 30, 30, 30 Weak blow on first opening only, recovered 10' drilling mud, no shows. IF 52/52 ICIP 74 FF 63/63 FCIP 63</p> <p>DST #2 4196-4230 (Viola) 30, 30, 30, 30, Weak blow, no blow on 2nd opening, Recovered 10' rotary mud, no shows. IF 52/52 ICIP 95 FF 52/52 FCLP 74</p>						

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or ~~Used~~

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"	24#	382.54'	Common	300 sx	3% C.C., 2% Gel.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Gravity

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	bbls.	MCF	%

Disposition of gas (vented, used on lease or sold)	Perforations